



Colorado Springs Utilities

It's how we're all connected

March 6, 2012

Mr. Dave Benbow
Pueblo County Department of Engineering & Public Works
33601 United Avenue
Pueblo, Colorado 81001

RE: Request to Install Sleeves in Roadway Crossings for Future Irrigation Line Use
Southern Delivery System (SDS) Raw Water Pipeline South 2 (RWP S2) Work Package
Pueblo West, Colorado

Dear Mr. Benbow,

The SDS Program would like to request the ability to install PVC conduits beneath the remainder of the roadway crossings located within the RWP S2 segment. This would allow for future use by our revegetation contractors as sleeves to run irrigation lines through.

The proposed conduits will consist of 4-inch, C900 DR 14, PVC installed from property line to property line beneath the 15 remaining road crossings listed below. The installed lengths are estimated at 100 feet per crossing. The conduits will be installed a minimum of 18 inches below each borrow ditch elevation and/or roadway (measured from the bottom of the base coarse material), whichever is greater. Each conduit will be installed in Type F granular bedding as described in Section 31 23 23.15, Subpart 2.01 D.6 of the RWP S2 Construction Specifications (consisting of clean crushed gravel or crushed rock, ¾-inch maximum particle size, being well graded from coarse to fine).

The above described conduit is proposed to be installed beneath the following roadways along the RWP S2 alignment in Pueblo West:

E. Kirkwood Dr.	N. Iliff Rd.	E. Sapinero Dr.
E. Sandusky Dr.	E. Platteville Blvd.	E. Ranch Dr.
E. Linda Dr.	E. Desert Cove Dr.	E. Paramount Dr.
E. Jaroso Dr.	E. Marengo Dr.	E. Ivanhoe Dr.
N. Purcell Blvd.	E. Sequoya Dr.	Industrial Blvd.

Upon completion of the revegetation activities, any irrigation lines installed in the conduits will be properly abandoned in place by the revegetation contractor.

We appreciate your consideration of this request. The first conduit installation is scheduled beneath Kirkwood Drive on Thursday, March 8. Thank you in advance and we look forward to your response.

Sincerely,
Colorado Springs Utilities

Joseph Rasmussen
Project Manager, RW S2
Southern Delivery System

JR
CC: B. Niznik, P. Hern, D. Auge, P. Tunnah, File

Reply Requested:
Yes No:
Date Required: 08-Mar '12

121 South Tejon Street, Third Floor
P.O. Box 1103, Mail Code 930
Colorado Springs, CO 80947-0930

Phone 719.668.4800
Fax 719.668.8734
<http://www.csu.org>